



October 4, 2019

BID BULLETIN NO. 1

This addendum is issued to modify or amend item/s in the Bidding Documents. This shall form as integral part of the Bidding Documents for the contractor:

Ref. No.	NAME OF PROJECT:	ABC (₱)	CONTRACT DURATION
	Mt. Province, Baguio, Benguet and Pangasinan District		
NHAR1CAR1-ROBAC-INFR-19-001	Land Development of Teacher's Camp Upgrading Project, Proclamation 613, Teacher's Camp, Baguio City	24,993,137.00	200 c.d.

Addendum No. 1 - POSTPONEMENT AND NEW SCHEDULE OF THE SUBMISSION AND OPENING OF BIDS

In view of the scheduled court hearing of the ROBAC Chairperson on October 8, 2019 and the NHA's Conferment of 2019 Loyalty Awardees to be held in Quezon City on October 9, 2019 at 9:00 a.m. which requires the attendance of the ROBAC Vice Chairperson, one (1) ROBAC Regular Member and the ROBAC Secretariat Head as loyalty awardees, all bidders who secured bidding documents and concerned parties are hereby informed of the postponement and new schedule of the submission and opening of bids at the same venue.

Activities	From	To
Submission and Opening of Bids	October 8, 2019 at 1:00 p.m.	October 15, 2019 at 9:00 a.m.

Addendum No. 2 - SUPPLICATION OF PROVISIONAL SUMS IN THE SCHEDULE OF BID RATES

ITEM NO.	DESCRIPTION OF WORKS	UNIT	QUANTITY	UNIT COST	TOTAL COST
A.3	Permits and Licenses Provisional sum for the application of permits (land development permit and Environmental Compliance Certificate) and other licenses needed for Land Development Works	PS			100,000.00
A.4	Office Equipment Supply of one (1) brand new All-in-one printer	PS			9,000.00

	project presentation, regular evaluation and monitoring of the project with the following requirements: Dual core 2.0GHz Intel Core i7 (Turbo Boost up to 3.2 GHz) with \$MB shared L3 cache; 512 GB, 13" LED Display, Bluetooth and WIFI capable; OS X (original); MS Office Software				
H	MISCELLANEOUS Provisional sum for testing of materials necessary for the land development works	PS			70,000.00

Attached herewith is the revised form of the schedule of Bid Rates.

For the information and guidance of all concerned.


ATTY. RONY A. LAGMAY
 Chairperson, ROBAC
 District Manager, ALUISIN

Project: **TEACHERS CAMP UPGRADING PROJECT**
LAND DEVELOPMENT WORKS
Location: Teacher's Camp, Baguio City

SCHEDULE OF BID RATES

ITEM NO.	DESCRIPTION OF WORKS	UNIT	QUANTITY	UNIT COST	TOTAL COST
A.	GENERAL REQUIREMENTS				
A.1	Mobilization/Demobilization Erection and dismantling of plant bunk houses and transporting of at least one of each of the following equipments from the contractor/developer's depot to the project site and vice versa : Dump Truck, Water Truck, Payloader, Grader, Vibratory Roller and provision of temporary facilities (Warehouse, Field Office)	LS			
A.2	SAFETY AND HEALTH Supply of materials, tools, and labor needed for the safety and health for the implementation of Teacher's Camp upgrading Project.	L.S			
A.3	Permits & Licenses Provisional sum for the application of permits (land development permit & Environmental Compliance Certificate) and other licences needed for Land Development Works.	PS			100,000.00
A.4	Office Equipment Supply of one (1) brand new All-in-one printer	PS	1.00		9,000.00
	Supply of one (1) brand new laptop computer for the use of the project implementation during project presentation, regular evaluation and monitoring of the project with the following requirements: Dual-core 2.0GHz Intel Core i7 (Turbo Boost up to 3.2GHz) with \$MB shared L3 cache; 512 GB, 13" LED Display, Bluetooth and WIFI capable; OS X (original); MS Office Software	PS	1.00		62,000.00
	Sub-total (General Requirements) >>>				
B.	SITE PREPARATION				
B.1	Clearing and Grubbing Supply material, labor and equipment necessary to complete this scope of work as specified in the plan.	sq. m.	6,932.00		
B.2	Site Filling Supply material, labor and equipment necessary to complete this scope of work as specified in the plan.	cu.m	1,500.00		
B.3	Tree Cutting/Planting Supply material, labor and equipment necessary to complete this scope of work as specified in the plan.	trees	60.00		
	Sub-total (Site Preparation)>>>				
C	ROADWORKS				
C.1	Subgrade Preparation This item shall consist of the preparation of the sub-base course for the support of the overlaying structural layers. It shall extend to full width of the carriageway including curb and gutter of the road	sq.m	4,740.00		
C.2	Item 201 (Base Course) This item shall consist of furnishing, placing & compacting of Item 201 (Base Course) on a cleared and prepared sub-base.	cu.m	1,114.00		

Project: **TEACHERS CAMP UPGRADING PROJECT**
LAND DEVELOPMENT WORKS
Location: Teacher's Camp, Baguio City

SCHEDULE OF BID RATES

ITEM NO.	DESCRIPTION OF WORKS	UNIT	QUANTITY	UNIT COST	TOTAL COST
C.3	Portland Cement Concrete Pavement (PCCP) This item shall consist of a Portland Cement Concrete Pavement constructed on a prepared base, in accordance with the plans, specs and in conformity with the typical cross sections shown on the plans, grades, thickness, typical cross sections shown on the plans PCCP (3000psi @ 28 days)	cu.m	1,256.00		
C.4	Construction of Curb and Gutter This Item shall consist of the construction of curb and gutter Cast in place, made of concrete in accordance with this Specification at the location, and in conformity with the lines, grades, dimensions and design, shown on the Plans	l.m	1,941.00		
C.5	Construction of Guardrail This item shall consist of furnishing and constructing guardrails in accordance with this Specification, at the locations, and in conformity with the lines and grades shown on the Plans	l.m	140.00		
	Sub-total (Roadworks)>>>				
D.	DRAINAGE WORKS				
D.1	Reinforced Concrete Pipe This item shall consist of the construction RCP canals, in accordance with this Specification and in conformity with the lines and grades shown on the Plans				
D.1.1	450 mm dia. RCP	l.m	805.00		
D.1.2	600 mm dia. RCP	l.m	505.00		
D.1.3	900 mm dia. RCP	l.m	24.00		
D.2	MANHOLE WITH COVER This item shall consist of the construction of manholes and inlets in accordance with this Specification and in reasonably close conformity with the lines and grades shown on the Plans				
D.2.1	450 mm dia. RCP	pcs	70.00		
D.2.2	600 mm dia. RCP	pcs	40.00		
D.2.3	900 mm dia. RCP	pcs	4.00		
D.3	OPEN CANAL Supply labor, materials and equipment to construct the open canal in accordance with the designed plans, details, & specifications as shown in the plan.	li.m	111.00		
	Subtotal (Drainage Works)>>>				
E.	STONE MASONRY Supply labor, materials and equipments to construct Stone Masonry (Stone Masonry with Apron and Fence) as specified in the plans.				
E.1	Stone Masonry with Apron	cu.m	102.00		
E.2	Fence	l.m	65.00		
E.3	Stone Masonry with Column and Beam	cu.m	280.00		
	Subtotal (Flood Protection)>>>				

Project: **TEACHERS CAMP UPGRADING PROJECT**
LAND DEVELOPMENT WORKS
Location: Teacher's Camp, Baguio City

SCHEDULE OF BID RATES

ITEM NO.	DESCRIPTION OF WORKS	UNIT	QUANTITY	UNIT COST	TOTAL COST
F.	BRIDGE CONSTRUCTION Supply labor, materials and equipments to construct Box Culverts (Bridge Type / One-celled Box Culvert) as specified in the plans.				
F.1	Box Culvert 1	set	1.00		
F.2	Box Culvert 2	set	2.00		
	Subtotal (Bridge Construction)>>>				
G.	LOT TITLING Supply labor, materials and equipments to check complete survey returns, process documents, notarial/legal services and other liason works				
		lots	135.00		
	Subtotal (Survey Works)>>>				
H.	MISCELLANEOUS Provisional sum for Testing of Materials necessary for the land development works.				
		PS			75,000.00
	Subtotal (Miscellaneous Works)>>>				
T O T A L (LAND DEVELOPMENT COST):					

Note: Estimated quantities are for purposes of evaluating bids only. Payments shall be based on actual quantities delivered, installed and constructed.

GRAND TOTAL

IN WORDS:

IN FIGURE:

Submitted by:

_____ Signature

_____ Name of Representative

_____ Name of Contractor